


### GIS as a Watershed Planning Tool

- Effective way to gather and process detailed data
- Effective way to interface with the public
  - Basic water quality education
  - Detailed project-related findings
- Planning and the identification of Priority Areas
- Reporting Tool

# Identification of Priority Areas



### Identification of Priority Areas


Pre-Project Winnebago River Watershed (229,161 acres) Estimated Sheet and Rill Erosion (RUSLE)

Minnesota Portion (45,606 acres)


Total Estimated Erosion = 37,797 tons/year Average Estimated Erosion = 0.83 tons/acre/year

Iowa Portion (183,555 acres)


Total Estimated Erosion = 252,869 tons/year Average Estimated Erosion = 1.38 tons/acre/year




### Identification of Priority Areas





### Projecting Land Use Changes






### Land Cover Assessments







### Pre-Project RUSLE - No Structures



### Pre-Project - Existing Structures



### Post-Project - Additional Structures



### RASCAL Assessments

### Pre-Survey


- Establishment of local Advisory Group
- Identification/ranking of priority water quality issues
- Send out letters to landowners
- Secure equipment


### Survey

- Receive training
- Respect landowners rights
- Ensure personal safety


### **■** Post-Survey


- Identify all physiologic & land use breaks
- Compare adjacent segments and combine
- Combine data for final segments with GIS data
- Describe on-going water quality threats by segment















### Farmers Creek In-Stream Assessment Livestock Access










- Flow Estimate
- Substrate
- Channel Condition
- Pool Frequency
- Bank Type
- Bank Height
- Bank Stability
- Bank Material


- Stream Habitat
- Losing Flow
- Riparian Cover
- Riparian Width
- Adjacent Land Use
- Livestock Access
- Canopy Cover
- Hydrologic Variability
- Channel Profile


#### **Farmers Creek RASCAL Segments**

Stream Segment	Streambank Stability	Substrate	Depositional Environment	Adequate Buffers	Livestock Access
А				X	
В	XX	XX			X
С		XX	X	X	
D	X			X	
Е	XX			X	X
F	X	XX	X		X
G	X				X
Н	XX	XX	X		X
I	X	XX	X	X	









#### **Stream Segment B**

This segment is characterized by moderately unstable stream banks, the cause of which may be unrestricted livestock access throughout much of this reach. Even though erosion rates in the surrounding cropland areas moderate somewhat, it appears this segment receives significant sediment from on-going rill & sheet erosion exported downstream from segment A. Couple this with a lessening of the channel gradient, the decreased flow rates are not sufficient to effectively transport the existing sediment load through the segment, thus most of the substrate is covered by silt/mud.

#### **Stream Segment C**

The stream banks throughout this segment appear to be stable, and livestock access very limited. However, overall soil losses from rill & sheet erosion increase, and there is a general lack of stream corridor vegetative buffers in this segment. The channel gradient continues to decrease, creating an even greater depositional environment, thus covering most of the substrate in this segment with silt & mud.

	Stream Segment								
ВМР	Α	В	С	D	Е	F	G	Н	
Upland Treatment Practices	X		X	X		X		X	X
Stream Corridor Fencing		X			X	X	X	X	
Stream Corridor Vegetative Buffers			X	X	X				X
Stream Bank Stabilization				X	X		X	X	
In-Stream Stabilization Practices		X	X			X		X	X
Storm Water Management Practices	X								

### Sediment Budgets

#### **Upper Catfish Creek Sediment Budget**

Erosion Source	Amount	Conversion Factor	Total Erosion (tons)	SDR	Sediment Delivered (tons/year)	% of Total Delivered
Rill & Sheet Erosion	9,300 ac.	*	20,809	26%	4,719 **	55%
Gully Erosion						
Cropland	3,537 ac	0.5 tons/ac.	1,769	70%	1,238	14%
Non-cropland						
Grass	1,447 ac.	0.35 tons/ac.	506	90%	455	23%
Timber	3,315 ac.	0.50 tons/ac.	1,658	90%	1,492	23 /0
Streambank Erosion						
Stable	4.91 mi.	15 tons/mi.	74	100%	74	
Moderately Stable	4.07 mi.	42 tons/mi.	171	100%	171	8%
Moderately Unstable	1.32 mi.	242 tons/mi.	319	100%	319	0 /0
Unstable	0.32 mi.	337 tons/mi.	108	100%	108	

**Total Sediment Delivered (tons/year) = 8,576** 

<sup>\*</sup> varies based upon values entered into GIS using Iowa DNR's notebook computer

<sup>\*\*</sup> adjusted to relfect sediment trapped in existing structures

# **Estimating Loading Reductions**

Erosion Source	Amount	Sediment Delivered (before)	Sediment Delivered (after)	% Reduction
Rill & Sheet Erosion	9,300 ac.	4,719 t/yr	3,580 t/yr	24%
Gully Erosion				
Cropland	3,537 ac	1,238 t/yr	650 t/yr	47%
Non-cropland				
Grass	1,447 ac.	455 t/yr	300 t/yr	34%
Timber	3,315 ac.	1,492 t/yr	950 t/yr	34%
Streambank Erosion				
Stable	4.91 mi.	74 t/yr	74 t/yr	0%
Moderately Stable	4.07 mi.	171 t/yr	150 t/yr	12%
Moderately Unstable	1.32 mi.	319 t/yr	250 t/yr	22%
Unstable	0.32 mi.	108 t/yr	50 t/yr	54%
	Totals	8,576 t/yr	6,004 t/yr	30%